

Fiscal Year	County	Jurisdiction	Project Name	Limits	Length	Primary Work Type	Project Description	Phase	Advance Construct	Federal Cost (\$000)	Federal Fund Source	State Cost (\$000)	State Fund Source	Local Cost (\$000)	Local Fund Source	Total Cost (\$000)	MDOT Job No.	Local ID No.	MPO/Rural Approval Date	Amendment Type	Air Quality	Comments	
2010	Berrien	MDOT	I-94	under Britain Avenue, Benton Harbor	0.552	Bridge replacement	Superstructure replacement	ROW		\$ 24,300	IM	\$ 2,700	M			\$ 27,000	104002						
2010	Berrien	MDOT	I-94	under Britain Avenue, Benton Harbor	0.552	Bridge replacement	Superstructure replacement	CON		\$ 4,990	HBOA	\$ 1,107	M			\$ 6,097	104002						
2010	Berrien	MDOT	I-94	44 th Avenue (CR 376) over I-196, Benton Center Road over I-94, 46 th Street over I-94	3.438	Bridge - Other	Concrete deep overlay, beam and substructure repair, bearing replacement, approaches	CON		\$ 3,299,079	BHI	\$ 366,564	M			\$ 3,665,643	107161						
2010	Berrien	MDOT	I-94 BL	at I-94 in Stevensville	0.010	Roadside Facility	Expansion and paving carpool lot	CON		\$ 93	ST	\$ 21	M			\$ 114	103292						
2010	Berrien	MDOT	I-94 EB	Sawyer Road to north city limit of Bridgman	5.000	Sawyer Road to North City Limits of Bridgman	Mill existing HMA and apply two course HMA resurfacing treatment. Widen outside shoulder to thirteen feet paved to maintain work zone traffic and meet FHWA guideline. Widen inside shoulder to ten feet wide to meet FHWA Standard. Flatten median slope, replacement of all median culverts and shallow cross culverts, re-install cable median barrier, guardrail upgrade, freeway signing upgrade, and ROW fence replacement. ROW may be required to complete drainage upgrade.	ROW		\$ 135	IM	\$ 15	M			\$ 150	79871						
2010	Berrien	MDOT	M-139	from 0.1 miles south of Hinchman Road to 0.3 miles north of the St. Joseph River	7.028	Trunkline Highway CPM/CSM GPA	Cold milling and 165#/syd one course HMA overlay	CON		\$ 1,473,301	NH	\$ 326,699	M			\$ 1,800,000	103173						
2012	Berrien	MDOT	I-94	at Nickerson Road, M-40 at M-43, and I-94 at M-40	0.011	Roadside Facility	Resurface carpool lots	CON		\$ 22	ST	\$ 5	M			\$ 27	103294						
2012	Berrien	MDOT	I-94	under John Beers Road	0.247	Trunkline Bridge CPM/CSM GPA	Full paint, Joint replacement	CON		\$ 362	BHI	\$ 40	M			\$ 402	88086						
2012	Berrien	MDOT	I-94 EB	from Red Arrow Highway for 1.6 miles east.	1.600	Resurface	Mill existing HMA and resurface at 5 inch depth, except add additional 3 inches of base course to I-94 EB outside and center lanes. Reconstruct outside shoulder to thirteen feet paved to maintain workzone traffic. Reconstruct inside shoulder to 10 feet wide paved. Erect cable median barrier. Replace all culverts draining the median and shallow cross culverts.	CON		\$ 7,380	IM	\$ 820	M			\$ 8,200	90362						
2013	Berrien	MDOT	I-94 EB	Sawyer Road to north city limit of Bridgman	5.000	Resurface	Mill existing HMA and apply two course HMA resurfacing treatment. Widen outside shoulder to thirteen feet paved to maintain work zone traffic and meet FHWA guideline. Widen inside shoulder to ten feet wide to meet FHWA Standard. Flatten median slope, replacement of all median culverts and shallow cross culverts, re-install cable median barrier, guardrail upgrade, freeway signing upgrade, and ROW fence replacement. ROW may be required to complete drainage upgrade.	CON		\$ 14,805	IM	\$ 1,645	M			\$ 16,450	79871						